



STRAND
ASSOCIATES®

Excellence in Engineering Since 1946

Strand Associates, Inc.®


WWTP Projects Build on Previous Work and Deliver Value and Cost Benefits

City of Chippewa Falls, WI



WWTP Needs


- 1. Biosolids (Sludge) Dewatering**
- 2. Influent Screening & Hauled Waste Receiving**
- 3. Biogas Reuse-Cogeneration**
- 4. User Charge System Update**
- 5. Funding – Grants and Low Interest Loans**



Sludge Dewatering Project

- **Sludge (Biosolids) are land applied as fertilizer**
- **Biosolids must be stored over the winter**
- **Existing equipment needs upgrading or replacement**
- **Planning report compared**
 - **Upgrading existing**
 - **Replacing with like equipment**
 - **Replacing with improved technology**
- **Replacing with new technology had lowest long-term costs**

Sludge Dewatering Project



Existing Belt Filter Press
(Dewatering Equipment)



Biosolids don't stack very well



Need more storage or
drier biosolids

Sludge Dewatering Project

Centrifuge Technology Will
Produce Drier Biosolids)



Screening & Septage Receiving

- Influent screen is very old – well beyond normal life
- Screen openings are large – inefficient at protecting WWTP
- Bypassing screen is labor intensive and puts staff in potentially dangerous situation
- Septage and hauled wastes can provide significant revenue
- Need to provide an efficient drop-off facility to increase business
- Need to charge fairly; shouldn't continue to work on the "honor system"
- This planning project will address both screening and septage receiving

Screening Facilities



Screening Facilities

Material gets caught on top of screen




Screenings are not compacted, or dry.

Screening Facilities

**Screen Structure is 30 Years Old;
Metal is Failing**



Septage and Hauled Waste Receiving



Septage and Hauled Waste Receiving



- Trucks cannot efficiently drop material off
- No storage at WWTP to protect plant
- No metering or auto-monitoring of wastes brought in
- Honor system – equitable?
- Zero interest financing available for these projects


Biogas Reuse – Cogeneration and Codigestion

- Existing microturbines have failed or are failing; normal life is only about 10 years
- Gas conditioning system is becoming more difficult to maintain
 - Media life has decreased
 - Equipment is becoming obsolete – expensive to custom build parts
 - Requires special electrical/HVAC rating (explosion potential)
- Can potentially increase gas production by bringing in high-strength wastes
- Could make more electricity
- Some grant funding is available on a case-by-case basis.

Biogas Reuse – Biogas Conditioning Equipment Requires Updates



Compressor (obsolete) and Conditioning Equipment



Lean-To to House Non-Rated
Biogas Refrigerated Dryer/Cooler

Biogas Reuse – Existing Microturbines Need Replacement



Biogas Reuse Will Look at Multiple Technologies



Microturbines



Engine Generator



CNG Compressing & Fueling

Biogas Reuse - Codigestion

- High-Strength Industrial Wastes
 - Cheese/dairy plants
 - Beverage and bottling plants
 - Food plants
- Fats, Oils, and Grease (FOG)
 - Grease traps
- Glycerin - biodiesel plants



Codigestion Benefits



- **Tipping Fees ~ \$0.00 - \$0.10/gal**
- **Higher biogas production**
- **Potential for COGEN at smaller plants (and larger plants)**

Codigestion - How Much Gas?

Example:

Volume: 5,000 gal/day

COD: 200,000 mg/L

COD Load: 8,340 lbs/day

COD Removed (80%): 6,700 lbs/day

Methane (CH₄): 37,520 ft³/day

Biogas (@ 60% CH₄): 62,500 ft³/day

Fond du Lac, WI – High-Strength Waste Receiving



Dubuque, IA



Project Engineering Budget

Dewatering Project - Design	\$80,000
Screening/Septage - Planning	\$20,000
Biogas-Cogeneration - Planning	\$18,000
User Charge System Update	\$8,000
Funding – Low Int. Loans and Grants	\$20,000
<hr/>	
Total	\$146,000
Total if All Done Together	\$141,000

Project Schedule

Start Dewatering Design	June 2014
Start Planning Projects	June 2014*
Complete Design	Fall 2014
Bid/Award Projects	Late Fall 2014
Submit Loan/Grant Appl.	Winter 2014/15
Complete Construction	Late 2015/Early 2016**

